

INDIAN INSTITUTE OF MANAGEMENT AMRITSAR

No. 33/IIM/ASR/2017/

Dated: 11-08-2017

NOTICE INVITING QUOTATION

Sealed item rate quotations are hereby invited on behalf of the Director, Indian Institute of Management Kozhikode. IIM Amritsar, PIT Building, Inside Govt. Polytechnic Campus, Polytechnic Road, Chheharta, G.T. Road, Amritsar from the contractors Registered with State P.W.D., C.P.W.D., M.E.S, Railway, for the work given below so as to reach this office up to 3:00 PM on 21-8-2017 which shall be opened on the same day at 3:30 P.M in the office as mentioned above in the presence of the quotationers/bidders or their representatives as present for the purpose. Quotation can be had from the office of Director, Indian Institute of Management Kozhikode. IIM Amritsar, PIT Building, Inside Govt. Polytechnic Campus on all working days from 10.00 AM to 4.00 PM till 19-08-2017.

This notice can also be seen on website www.iimamritsar.ac.in.

Sr.No.	Name of Work	Estimated cost	Time allowed	Last date & time of submission of Quotation	Date & time of opening of quotation
1	Provision of miscellaneous services to the mess and external area of transit campus of IIM Amritsar.	129759/-	15 days	21-08-2017 up to 3.00 PM	21-08-2017 at 3.30 PM

Terms and Conditions:

1. An Earnest Money (EMD) of Rs. 2600/- (Rs.Two thousand six hundred only) in the form of DD / FDR in favour of IIM Amritsar is to be annexed with their bids failing which quotation will not be considered.
2. No Bidder shall be allowed to withdraw the quotation. In case of withdrawal, the EMD shall stand forfeited.
3. EMD of unsuccessful bidders shall be refunded after issuance of work order. EMD of successful bidder shall form the part of security deposit.
4. The work shall be carried out as per CPWD specifications amended upto date and as per directions of Engineer-in-Charge.
5. The rates quoted shall be inclusive of all taxes and levies including GST and nothing extra shall be payable on this account.
6. The material shall be got approved from the Engineer-in-Charge prior to use at site.
7. No tools and plants shall be issued by the department for this work.
8. The time allowed for the completion of the work is 30 Days after date of written orders to commence the work.
9. The payment shall be made by the IIM Kozhikode.
10. Income Tax & GST as applicable shall be deducted from the bill.
11. Nothing shall be paid for oversized dimensions than specified in the drawings.
12. The quotation shall be valid for a period of 30 days.
13. The quantities taken in the quotation are tentative & payment shall be made as per quantities actual executed at site.
14. Labour Cess @1% on value of work done shall be deducted from the bill of the agency.
15. Work order shall be issued in Form CPWD 11A.
16. Documentary proof for the constitution of tenderer firm with details of the name, address, telephone number to be submitted with bid.
17. The Competent authority reserves the right to reject any or all of the quotation without assigning any reason.
18. The Security deposit shall be deducted at the rate of 5% which shall be retained for a period of three months.

Schedule of Quantities

Name of Work:-Provision of miscellaneous services to the mess and external area of transit campus of IIM Amritsar.

Sr. No.	Description of Item	Qty	Unit	Rate		Amount
				In fig	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	0.5	Cum			
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	0.5	Cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size).	0.1	Cum			
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	1.6	Cum			
5	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm	18	Sqm			
6	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work	18.5	Metre			
7	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	+	Labour			
8	Providing and fixing ply board exterior grade to frame, backing or studding with screws etc. complete (Frames, backing or studding to be paid separately): 12 mm thick	4	Sqm			
9	Providing and fixing commercial ply board in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 18 mm thick	5	Sqm			
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	72	Kg			

11	<p>35 mm thick factory made Solid panel PVC Door shutter, made out of single piece extruded solid PVC profiles, 5 mm (± 0.2 mm) thick, having styles & rails (except lock rail) of size 95 mm x 35 mm x 5 mm, out of which 75 mm shall be flat and 20 mm shall be tapered (on both side), having one side thickness of 15 mm integrally extruded on the hinge side of the profile for better screw holding power, including reinforcing with MS tube of size 40 mm X 20 mm x 1 mm, joints of styles & rails to be mitered cut & joint with the help of PVC solvent cement, self driven self tapping screws & M.S. rectangular pipes bracket of size 190 mm X 100 mm of cross section size 35 mm x 17 mm x 1 mm at each corner. Single piece extruded 5 mm thick solid PVC Lock rail of size 115 mm x 35 mm, out of which 75 mm to be flat and 20 mm to be tapered at both ends, having 15 mm solid core in middle of rail section integrally extruded, fixing the styles & rails with the help of solvent and self driven self tapping screws of 125 mm x 11 mm, including providing 5 mm Single piece solid PVC extruded sheet inserted in the door as panel, all complete as per manufacturer's specification and direction of Engineer-in-charge. Non decorative finish (matt finish)</p>	1.90	Sqm
12	<p>Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.</p>	3.50	Sqm
13	<p>15 mm cement plaster on the rough side of single or half brick wall of mix :1:4 (1 cement: 4 fine sand)</p>	8	Sqm
14	<p>Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :</p> <p>Kitchen sink with drain board 510x1040 mm bowl depth 250 mm</p>	1	Each