

Ref No. IIM-Asr/oldcmps/1/20 -185

Date: -13.07.20

**CORRIGENDUM 2**

This is to inform to all that following changes have been made in the call of quotation no. IIM-ASR/oldcmps/1/20/182 dtd 06.07.2020 for maintenance work at transit campus of IIM Amritsar.

**Annexure I**

Sr. no.	Description	Units	Qty.	Rate	Amount
1	<b>PAINTING</b>				
a	Distempering with oil bound washable distemper of approved brand and manufacture in two coats including brushing, sand papering, filling putty in holes wherever required to give an even shade.(Approved brand – Asian, Nerolac, Berger, Dulux )	Sqm	1300		
2	<b>TILING WORK IN DADO</b>				
a	Providing and fixing 1 <sup>st</sup> quality ceramic glazed tiles of approved make in matching colours and sizes of the existing nearby tiles in dados over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry including pointing in white cement mixed with pigment of matching shade complete. (Approved brand – Somany, Kajaria)	Sqm	25		
3	<b>TILING WORK ON FLOOR</b>				
a	Providing and fixing 1 <sup>st</sup> quality ceramic glazed floor tiles of approved make in matching colours and sizes of the existing nearby tiles in floor over 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand) and jointing with grey cement slurry including pointing in white cement mixed with pigment of matching shade complete. (Approved brand – Somany, Kajaria)	Sqm	2		
4	<b>REINFORCED CEMENT CONCRETE</b>				



**IIM**  
AMRITSAR

# INDIAN INSTITUTE OF MANAGEMENT AMRITSAR

Punjab Institute of Technology, Inside Government Polytechnic Compound,  
Chheharta, GT Road Amritsar- 143105, Phone: 0183-2820034

a	Providing & laying reinforced cement concrete shelves in 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm down size)  (Cement – OPC 43 grade)	Cum	3		
b	Providing centering and shuttering including strutting, propping, etc. complete and removal of form for shelves	Sqm	36		
c	Providing & laying steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete with Thermo-Mechanically Treated bars of grade 500D or more of approved brand.  (Approved brand – Sail, Tata)	Kg	350		
5	<b>GRANITE ON KITCHEN SLAB</b>				
a	Providing & laying 18 mm thick polished Granite stone of approved colour over 20 mm average thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing & polishing etc. all complete as specified.	Sqm	23		
b	Providing & making nosing to the Granite stone slab including rubbing, curing & polishing etc. for smooth finish.	Metre	25		
6	<b>ALUMINIUM WORK BELOW KITCHEN SLAB</b>				
a	Providing & fixing aluminium work below kitchen slab same as the existing ones consisting of following: -  (a) 16 gauge powder coated aluminium frame in brown colour, & (b) 12 mm thick PVC board of approved colour & shade.  Note: - Bidders are suggested to visit the existing canteen before quoting to have the idea of this work.	Sqm	20		
7	<b>KITCHEN SINK</b>				




IIM  
AMRITSAR

# INDIAN INSTITUTE OF MANAGEMENT AMRITSAR

Punjab Institute of Technology, Inside Government Polytechnic Compound,  
Chheharta, GT Road Amritsar- 143105, Phone: 0183-2820034

a	Providing & fixing heavy duty Stainless Steel A ISI 304 (18/8) kitchen sink of size 610x510 mm bowl depth 200 mm with all accessories such as C.I. brackets, stainless steel plug, waste pipe, painting of fittings and brackets, etc., cutting and making good the walls wherever required, complete in all respect, including all connections & cost of fittings.	Nos	4		
<b>GST @</b>					
<b>GRAND TOTAL</b>					

The rest of the Terms and conditions will be remain same.

  
(Simrandeep Singh Thapar)  
Programme Officer

